GENERAL NOTES

1. STEAM METER TO BE INSTALLED A MINIMUM OF 36" ABOVE FINISHED FLOOR. STEAM METER TO BE INSTALLED NEAR WALL OR IN AN AREA WITH 24" X 24" CLEARANCE OF SPACE BELOW IT TO MOUNT A RACK FOR PROCESS CONTROLS.
2. METER TO BE INSTALLED SO THE TRANSMITTER HEAD IS AT A DOWNWARDS ANGLE BETWEEN 30 AND 45 DEGREES.

KEY NOTES

1. PROVIDE A MINIMUM OF 15" OF CLEARANCE FROM A WALL OR OTHER OBSTRUCTIONS FOR PROCESS PIPING.

STEAM METERING MECHANICAL PIPING DETAIL

1 / M1.01

SCALE: NO SCALE

Detail Title:	Detail No.:	33 63 00 - 05	Facilities, Planning & Capital Programs Standard Detail	University of Nebraska Lincoln
Steam Metering Mechanical Piping Detail	Scale:	N.T.S.		
	Date:	July 2023		